BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2020-21/OW/WORK_INDENT45961

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/11/2020-21, Date: 05-12-2020

Name of Work:Development of Secondary Drains in ward no 06

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of SANTHOSH VENKATAPURA CHANNAKESHAVA ( )	
				In Figures	In Words
1	85.98	Earthwork in execavation for foundation of structure like culverts, retaining wall etc., as per drawing and technical specification, including setting out, construction of shoring and bracing, dressing of sides and bottom, back filling with approved material, disposal of balance earth as per specification, including cost of labour, HOM etc., complete. In all kinds of soil by manual means. (P.No.256, I.No.34.15.1 of PW,P&IWTD S.R 2018-19)	Cum	196.73	Rupees One Hundred Ninety Six and Seventy Three Paise Only
2	7.92	KSRB 4-1.2: Providing and laying in position plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with 40mm nominal size mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days complete as per specifications, MORTH specifications No. 408, (P.No.13, I.No.4-1.2 of PW,P&IWTD S.R 2018-19)	Cum	3961.85	Rupees Three Thousand Nine Hundred Sixty One and Eighty Five Paise Only
3	7.92	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. With 20mm and sown size granite metal course aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compcted for walls and bottom including centring shuttering cost of material HOM of machinary curing etc., complete execluding cost of steel as per MORTH specification no. 1500, 1700, 2200 including cost of material labour HOM complete as per specification. (P.No.271, I.No.37.59.2 of PW, P&IWTD S.R 2018-19) wall & bottom thickness 15cm.	Cum	4152.55	Rupees Four Thousand One Hundred Fifty Two and Fifty Five Paise Only
4	85.2	KSRB 5-11 : Providing and constructing load bearing wall with having block density not less than 1800 kg/m3 and having a minimum average compressive strength 5.00 N/mm2 confirming to IS 2185 (Part 1):2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials labour charegs, scaffolding, curing, hire charges of machineries etc., complete as per specifications. KBS No.5.4 .-do- solid concrete blocks of size 400x150x200 mm (Page No.27. litem no.5.27.2 of KPWD S.R Bangalore Circle (2018-19)	Sqm	726.92	Rupees Seven Hundred Twenty Six and Ninety Two Paise Only
5	8.52	KSRB 4-1.1: Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No.13, I.No.4.1 of	Cum	4029.74	Rupees Four Thousand Twenty Nine and Seventy Four Paise Only
6	85.2	Providing and fixing RCC Precast cover slab of 100mm thick for drain in cement concrete M20 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge. (Data Rate)	Sqm	1681.7	Rupees One Thousand Six Hundred Eighty One and Seventy Paise Only

Santhosh

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92